

CA623/2



connectwell
THE RIGHT CONNECTION

Pre Assembled Shorting Links

Internal Shorting Link Assemblies consist of a Current Bar shorting Sleeves and Screws. They install easily into the center of the Terminal Block and connect to the current bar. They are available as standard 2, 3, 4, 10 or 100 pole assemblies and are ready for immediate installation.

PRODUCT SPECIFICATION

Rated Current	32 A
Torque	0.4 Nm

ORDERING INFORMATION

CAT. NO.	DESCRIPTION	STD. PACK
CA623/2	Pre assembled Shorting Link for 2 way shorting	100
CA623/3	Pre assembled Shorting Link for 3 way shorting	100
CA623/4	Pre assembled Shorting Link for 4 way shorting	100
CA623/10	Pre assembled Shorting Link for 10 way shorting	10

SUITABLE FOR

CTS4USC	4 sq.mm Spring Loaded Feed Through Terminal Blocks
CHV4U	4 sq.mm High Voltage Terminal Blocks.