

ca749/2


connectwell
 THE RIGHT CONNECTION

Insulated Pre Assembled Shorting Links

Internal Shorting Link Assemblies consist of a Current Bar shorting Sleeves and Screws. They install easily into the centre of the Terminal Block and connect to the current bar. They are available as standard 2, 3, 4, 10 or 100 pole assemblies and are ready for immediate installation. Insulated Preassembled internal Shorting link assemblies provide shock protection when installed on Terminal Blocks. Insulated pre assembled shorting link assemblies provide shock protection when installed on Terminal Blocks.

PRODUCT SPECIFICATION

Rated Current	32 A
Torque	0.5 Nm

ORDERING INFORMATION

CAT. NO.	DESCRIPTION	STD. PACK
CA749/2	Insulated Pre assembled Shorting Link for 2 way shorting	100
CA749/3	Insulated Pre assembled Shorting Link for 3 way shorting	50
CA749/4	Insulated Pre assembled Shorting Link for 4 way shorting	50
CA749/10	Insulated Pre assembled Shorting Link for 10 way shorting	10

SUITABLE FOR

DDDL4U	4 sq.mm Disconnect & Test Terminal Blocks with disconnecting link.
DDDL4ULR	4 sq.mm Disconnect & Test Terminal Blocks with disconnecting link.
DDFL4U	4 sq.mm Double Level Fuse Terminal Blocks.
DDFL4ULR	4 sq.mm Double Level Fuse Terminal Blocks with two equi-potential points on each side.
DDFL4UELR	4 sq.mm Double Level Fuse Terminal Blocks with two equi-potential points on each side and offline LED indication.
DDFL4UE	4 sq.mm Double Level Fuse Terminal Blocks with offline LED indication.