

CA729/2



connectwell
THE RIGHT CONNECTION

Pre Assembled Shorting Links

Internal Shorting Link Assemblies consist of a Current Bar shorting Sleeves and Screws. They install easily into the centre of the Terminal Block and connect to the current bar. They are available as standard 2, 3, 4, 10 or 100 pole assemblies and are ready for immediate installation.

PRODUCT SPECIFICATION

Rated Current	32 A
Torque	0.5 Nm

ORDERING INFORMATION

CAT. NO.	DESCRIPTION	STD. PACK
CA729/2	Pre assembled Shorting Link for 2 way shorting	100
CA729/3	Pre assembled Shorting Link for 3 way shorting	50
CA729/4	Pre assembled Shorting Link for 4 way shorting	50
CA729/10	Pre assembled Shorting Link for 10 way shorting	10

SUITABLE FOR

DDFL4UE	4 sq.mm Double Level Fuse Terminal Blocks with offline LED indication.
DDDL4U	4 sq.mm Disconnect & Test Terminal Blocks with disconnecting link.
DDDL4ULR	4 sq.mm Disconnect & Test Terminal Blocks with disconnecting link.
DDFL4U	4 sq.mm Double Level Fuse Terminal Blocks.
DDFL4ULR	4 sq.mm Double Level Fuse Terminal Blocks with two equi-potential points on each side.
DDFL4UELR	4 sq.mm Double Level Fuse Terminal Blocks with two equi-potential points on each side and offline LED indication.